

17'-0"

ELEVATION VIEW

GRADE

,0

0 0 0 0 0

(2


REINFORCING STEEL SCHEDULE								
ITEM	LOCATION	NO. REQ'D.	BAR SPC'G.	SIZE	CUT LGTH.	TOTAL LGTH.	TOTAL WT.	SHAPE
1	PAD TOP REINFORCING	44	EQUALLY SPACED	#5	16'-6"	726'-0"	757 LBS.	STRAIGHT
2	PAD BOTTOM REINFORCING	44	EQUALLY SPACED	#5	16'-6"	726'-0"	757 LBS.	STRAIGHT
3	PIER VERTICAL REINFORCING	30	EQUALLY SPACED	#6	4'-9"	142'-6"	214 LBS.	
4	PIER TIES	18	SPACED 10" C/C	#4	7'-6"	135'-0"	90 LBS.	2'-0" 0.D.
TOTAL REBAR WT.					1818 LBS.			

ANCHOR BOLT SCHEDULE						
ITEM	PART NO.	NO. REQ'D.	ANCHOR BOLT SIZE	SPACING		
5	C40041057	12	3/4 ø X 3'-3"	SEE PLAN		

FIELD NOTE

SEE DRAWING LDA00318 FOR LEG TO LEG TEMPLATES.

CONCRETE REQ'D	ROUND PIERS	SQUARE PIERS		
PAD	16.06 CU. YDS.	16.06 CU. YDS.		
PIERS	1.64 CU. YDS.	2.08 CU. YDS.		
TOTAL	17.70 CU. YDS.	18.14 CU. YDS.		



REBAR DETAIL


(PIER VERTICAL REBAR)

GENERAL NOTES


- 1. CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3000 PSI, IN ACCORDANCE WITH ACI 318-05. (2 REBAR TIES REQ'D IN THE TOP 5")
- 2. REBAR TO CONFORM TO ASTM SPECIFICATION A615 GRADE 60.
- 3. ALL REBAR TO HAVE A MINIMUM OF 3" CONCRETE COVER.

All rights reserved.

- 4. ALL EXPOSED CONCRETE CORNERS TO BE CHAMFERED 3/4".
- 5. SEE THE GEOTECHNICAL REPORT FOR COMPACTION REQUIREMENTS, IF SPECIFIED.
- 6. THE FOUNDATION DESIGN IS BASED ON AN ALLOWABLE BEARING PRESSURE OF AT LEAST 2 KSF. THE ADEQUACY OF THE SOIL MUST BE VERIFIED BEFORE INSTALLING THE FOUNDATION.
- 7. ONE ANCHOR BOLT MUST BE ALIGNED DIRECTLY WITH THE CENTER OF THE TOWER (TYPICAL).



DRW CHK



DESCRIPTION

CONFIDENTIAL
This document and the information contained herein is the confidential trade secret property of Sabre Communications Corporation ("Sabre") and must not be reproduced, copied or used, in whole or in part, for any purpose without the prior written consent of Sabre.

© 2010 Sabre Communications Corporation.

MODEL S3A SERIES LDA FOUNDATION INSTALLATION SECTION 18

		SIZE	DRAWING NO.		REV	
DATE 02/01/10		В	LDA00418		0	
DRAWN BY	WRF	<u> </u>		SCALE	PAGE	
CHECKED BY	KLE			NONE	1 OF 1	